



Westlake Academy Athletic Upgrades

Gym Building:

(1) Locker Rooms (700 SF):

- Remove Existing Showers and relocate restrooms to increase team area (“halftime space”)
- Update all finishes
 - o New Full Height Tile Wall and Flooring
 - o Paint Ceilings
 - o New Restroom Partition for due to new layout (assume Stainless Steel)
 - o New Quartz Countertops and Undermount Sinks
 - o Automatic Fixtures, Faucets and Accessories
 - o New LED recessed lighting and decorative sconces at sinks

(2) Public Restrooms (450 SF):

- Update all finishes
 - a. New Full Height Tile Wall and Flooring
 - b. Paint Ceilings
 - c. New Restroom Partitions
 - d. New Quartz Countertops and Undermount Sinks
 - e. Automatic Fixtures, Faucets and Accessories
 - o New LED recessed lighting and decorative sconces at sinks

Gymnasium (7750 SF):

- (3) Remove and Replace existing wood bleachers
 - a. New Wood Bleachers to have integrated wood storage at Exposed ends
- (4) Install 2” Acoustic wall panels on Upper portion of long walls
- (5) Replace Light fixtures in Gym with LED fixtures
- (6) New Digital Basketball Goals
- (7) Install New Volleyball standards to allow for 2 courts
- (8) Replace drinking fountains with bottle filler, replace wood flooring under drinking fountain with resilient flooring
- (9) Install New Track Mounted Rolling High Density Athletic Equipment System at storage room

Field House:

Locker Rooms (2850 SF):

- (10) Replace smaller lockers with larger lockers, club style lockers
- (11) Update all finishes
 - a. New Full Height Tile Wall and Flooring (including added flooring in locker area)
 - b. Paint Ceilings



- c. New Quartz Countertops and Undermount Sinks
- d. Automatic Fixtures, Faucets and Accessories
- o New LED recessed lighting and decorative sconces at sinks

Storage (780 SF):

(12) Install New Track Mounted Rolling High Density Athletic Equipment System at storage room

Coaches Suite (575 SF):

(13) Update finishes and lighting at locker rooms

- a. New Full Height Tile Wall and Flooring
- b. Paint Ceilings
- c. New Quartz Countertops and Undermount Sinks
- d. Automatic Fixtures, Faucets and Accessories
- o New LED recessed lighting and decorative sconces at sinks

(14) Install wood club style lockers

(15) Add millwork in coaches open office

Public Restrooms (250 SF):

(16) Update finishes and lighting at locker rooms

- a. Add Full Height Tile Wall and Flooring
- b. Paint Ceilings
- c. New Quartz Countertops and Undermount Sinks
- d. Automatic Fixtures, Faucets and Accessories
- o New LED recessed lighting and decorative sconces at sinks

Training Room (440 SF):

(17) Add whirlpool tub(s)

- a. Infrastructure already was installed for 1 tub
- b. Alternate to add a second tub (1 hot, 1 cold)

(18) Add Tile Flooring

(19) Install New built In Storage Units



Fields:

- (20)Astroturf for football field
- (21) Astroturf for Soccer field
- (22) Covered permanent Shelters (2) for soccer teams at soccer field
- (23)Install Shade Cover for the sports courts
- (23)Add (2) basketball goals on sports court